

**DRILLING OF HAND PUMPS AND INSTALLATION OF EQUIPMENTS AT**N.O.W: **GORHADHAKA**Estimated cost: **0.300 (M)**E / Money: **2%****BILL OF QUANTITY**

<b>S. No.</b>	<b>Description</b>	<b>Quantity</b>	<b>unit</b>	<b>Rate</b>	<b>Amount</b>
1	Mobilization of boring plant and equipment, camping arrangements going and return etc: complete.	1	P.M		
2	Boring of hand pump in all kind of soil 6" dia below ground level .				
	(a) (except shingle or gravel from 0-100 feet depth)	30.48	P.M		
	(b) (From 100-200 feet)	11.35	P.M		
3	Supply and laying of 4" i/dia PVC "B" class working pressure i/c strainer complete with carriage upto site and required fittings.	42.46	Per meter		
4	Providing and installation of PVC pipe with wooden ball plug pressure pumps BSS class "B" working pressure 4" dia 2 feet long in bore hole.	1	Per No.		
5	Shrouding of pressure pump with graded material as per approved by Engineer incharge complete.	1	Per Job		
6	Providing / installation of Hand Pump complete in all accessories.	1	Per No.		
7	PCC (1:2:4) as block of hand pump complete i/c screening and washing of stone aggregate.	0.43	Per M3		
<b>TOTAL</b>		<b>=</b>			

**CONTRACTOR'S STAMP / SIGNATURE**