

N.O.W:

REPAIR OF STREET LIGHTS IN GDA TOWNS.**BILL OF QUANTITY.****Estimated Cost:****3.509 (M)****Earnest Monty:****2%**

S.NO.	DESCRIPTION	QUANT ITY	UNIT	RATE	AMOUNT
1	S/F of street light sogo energy saver 45 watt, holder proclien, cost of internal cable/connection/clamp as directed by Engineer Incharge.	55	Nos.		
2	S/F of energy saver 45 watt Philips / SOGO i/c labour charges etc complete in all respect as directed by Engineer Incharge.	150	Nos.		
3	S / Laying cable excavation/refilling for cable trench size 9"x9"x12", cost of sand, cost of bricks i/c labour charges as directed by Engieer Incharge.	1665	M		
4	S / F main panel size 12"x15"x9" GI 16 SWG openable/lockable door, cost of main C.B 30-A TP, cost of CBSP 30-A (3 x 500) cost of bush brass internal wiring i/c labour charges complete in all respect as directed by Engineer	12	Nos.		
5	Conversion of already installed street lights cost of energy saver 45 watt cost of proclien holders, cost of internal light wiring cable connection i/c labour charges as directed by Engineer Incharge.	115	Nos.		
6	S/F hood light with 45-Watt energy saver light fixture, cost of hood light fixture sogo cost of street light pole i/c 2" dia G.I Pipe 7 feet high/ excavation fixing with concrete /labour charges as per instruction of Engineer Incharge	10 Lights	Nos.		
7	Repair Garden lights in plaza park, cost of energy saver repair/replacement internal wiring cable, labour charges as directed by Engineer Incharge.	09 Lights	Nos.		
8	Repair of telted pole, cost of balanceable pole i/c concrete in all respect labour charge as directed by Engineer Incharge.	70	Nos.		

9	Repair of damage pole cost of nut bolts, welding etc complete as directed by Engineer Incharge.	35	Nos.		
10	Repair / Allignment/welding of already installed light cost of welding/Allignment of street light & fixing, labour charges as directed by Engineer Incharge.	200	Nos.		
11	Supply and Erection single phase imported auto circuit breaker 20 Amp.	20	Each		
12	Insulation tape large size (Nito).	50	Each		
13	Wiring of main & sub-main in 2 single core PVC insulated & sheathed cable : 7/0.029	1500	M		
14	Wiring of main & sub-main in 2 single core PVC insulated & sheathed cable : 3/0.029	1500	M		
15	Supply and Erection single phase imported auto circuit breaker 15 Amp.	30	Each		
16	Push Botton	50	Each		
17	Electric Socket	50	Each		
18	Electric Holder Thread type (Fico).	75	Each		
19	Power Plug	35	Each		
20	Light Plug	25	Each		
21	Screw Driver set	2	Set		
22	Rench 12" size	5	Each		
23	Sodium Bulb 250 watt (Philips)	60	Each		
24	Energy Saver assembly i/c bulb energy saver 45 watt (Philips), Cool day light with pipe complete	100	Each		
TOTAL		=			

CONTRACTOR,S STAMP/SIGNAT URES