

N.O.W: **SNOW CLEARANCE OF RAODS IN GDA AREA 2015-16.**

Estimated Cost: Rs.5,000,000/-  
 Earnest Money: Rs.100,000/-  
 Time Limit: 15.12.2015 to 15.04.2016.

**NATHIAGALL.**

Church chowk to Governor House.	28	x	100	=	2800Rft
//	1	x	50	=	50Rft
Highway House Road.	4	x	100	=	400Rft
Exchange to Green Spot .	32	x	100	=	3200Rft
Pine cottage Road	6	x	100	=	600Rft
Main Mochidhara Chowk to Shangrillah Chowk	90	x	100	=	9000Rft
Green Hotel Road to Farooq Rehmatullah House.	6	x	100	=	600Rft
Pasha House to Taj Mahel site (Bazar).	8	x	100	=	800Rft
Mufti House Chowk to Green Hotel.	39	x	100	=	3900Rft
Church Chowk to Retreat House.	5	x	100	=	500Rft
//	1	x	100	=	100Rft
Green Spot Road to Bhatian.	3	x	100	=	300Rft
Plaza Park to Ikramullah House Road.	4	x	100	=	400Rft
DB House Internal Road.	4	x	100	=	400Rft
FWO Office.	2	x	100	=	200Rft
Club Link Road.	1	x	100	=	100Rft
DG House to Dr. Farhat.	3	x	100	=	300Rft
Masood Shah Orakzai House.	2.35	x	100	=	235Rft
Fancy Cloth House Road.	1	x	100	=	100Rft
Shangrilla Pine Hotel.	4	x	100	=	400Rft
Mochidhara to Hospital.	4	x	100	=	400Rft
Mochidhara to Hospital.	1	x	50	=	50Rft
Nathiagali Bazar to Govt: Degree College.	15	x	100	=	1500Rft

**GHORADAKA.**

Main Road to PTDC Hotel.	1	x	100	=	100Rft
//	19	x	100	=	1900Rft
PTDC Hotel Parking	1	x	80	=	80Rft
//	1	x	30	=	30Rft
Montana Lodge Parking.	1	x	86	=	86Rft
Mountina Lodge Road.	4	x	100	=	400Rft
VIP Chairlift Parking.	1.37	x	100	=	137Rft
VIP Parking to Post Office.	4	x	100	=	400Rft
Gen: Car Parking.	1.46	x	100	=	146Rft
Tariq Hayyat House Road.	1.5	x	100	=	150Rft
GDA Store To House of Dr. Jamil.	1	x	100	=	100Rft
Post Office Chowk to GDA office.	21	x	100	=	2100Rft
Gora Qabristan Road.	14	x	100	=	1400Rft
Main Road to Baniyamin House.	12	x	100	=	1200Rft

**CHANGLAGALI.**

Main Road to Chandmari.	52	x	100	=	5200Rft
//	1	x	100	=	100Rft
//	1	x	100	=	100Rft
Legard Hotel to Major Mukhtiar.	10	x	100	=	1000Rft
PEPSI House Road.	5	x	100	=	500Rft
Sada Bahar House.	6	x	100	=	600Rft
Legard Hotel to Cheema House.	2	x	100	=	200Rft
//	10	x	100	=	1000Rft

<b><u>KHAIRAGALI.</u></b>						
Gen: Alam House to Bazar.	8	x	100		=	800Rft
Khairagali Bazar to Hospital.	18	x	100		=	1800Rft
//	1	x	35		=	35Rft
Hospital to Gen Masood Alam.	10	x	100		=	1000Rft
Karachi House to Mosque.	6	x	100		=	600Rft
HospitalChowk to Play Ground.	23	x	100		=	2300Rft
Play Ground to Swargali Road.	5	x	100		=	500Rft
Play Ground to Plot No. 84-D.	6	x	100		=	600Rft
//	1	x	100		=	100Rft
<b><u>KHANSPUR.</u></b>						
GDA Rest House.	3	x	100		=	300Rft
//	1	x	100		=	100Rft
Civil Hospital Road.	13	x	100		=	1300Rft
Plot 31 to Shamas House.	6	x	100		=	600Rft
Childern Park to Kashmir View.	15	x	100		=	1500Rft
National Bank to Gul Nawaz House.	7	x	100		=	700Rft
Exchange Road.	6	x	100		=	600Rft
Play Ground to Plot No.31	38	x	100		=	3800Rft
<b><u>DOONGAGALI.</u></b>						
Main Road to Akram Durani House.	32	x	100		=	3200Rft
Sliman Dewan to Shahid Rafii.	7	x	100		=	700Rft
//	1	x	100		=	100Rft
Hamza Shahbaz House to Main Road.	18	x	100		=	1800Rft
Children Park to Brig Arshad.	7	x	100		=	700Rft
Main Road to Wild Life.	1	x	100		=	100Rft
//	7	x	100		=	700Rft
Main road to Bashir Bilour House.	7	x	100		=	700Rft
Public Health Rest Hosue.	8.5	x	100		=	850Rft
<b><u>THANDIANI.</u></b>						
Inspection Banglow C&W to Pattan Kalan Road.	107	x	100		=	10700Rft
	1	x	50		=	50Rft
Main Road to PTV Booster.	4	x	100		=	400Rft
PTCL Road.	3	x	100		=	300Rft
Main Road to PMA Point.	8	x	100		=	800Rft
					=	80999Rft
					=	25Kilomiter

## II SCOPE OF WORK:

### a. Length of Road:-

All Roads should be cleared against Snow/Land slides/Avalanches & any other obstruction like falling of trees/electric poles etc on road surface upto the length of road covered/closed by the intensity of snow fall or as directed by Engineer Incharge.

### b. Width of Road:-

All roads should be cleared against Snow/Land slides/Avlanches upto a minimum width of 4 meter at straight traches while a minimum width of 5 to 6 meter should be cleared at curves, or at every 150 meter intervals for crossing of vehicles thugh out the effected length of the road or as direecterd by Engineer Incharge.

### c. Spreading of Salt:-

All roads should be cleared against frosty reaches by spreading salt as and when required or as directed by Engineer Incharges.

**III MODE OF PAYMENT.**

<b>S.NO.</b>	<b>DATE/MONTH</b>	<b>VALUE OF CONTRACT IN (M)</b>	<b>PAYMENT TO BE RELEASED IN (%AGE)</b>	<b>AMOUNT IN MILLION.</b>
<b>1</b>	Last Week of December 2015		15%	
<b>2</b>	Last Week of January 2016		35%	
<b>3</b>	Last Week of February 2016		25%	
<b>4</b>	On Successful completion of the work.		25%	
<b>TOTAL =</b>			<b>100%</b>	

**SIGNATURE OF THE CONTRACTOR:**