

Estimated Cost: **Rs.1,083,000/-**
E/Money: **Rs.21,660/-**

BILL OF QUANTITY

Name of Work: **SPECIAL REPAIR OF STEEL TANKS IN GDA TOWN.**

S. NO.	DESCRIPTION	UNIT	RATE
1	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:4:8)	P.M3	
2	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:2:4)	P.M3	
3	Repair of leakage with M.S sheet 14 SWG including welding etc complete as directed by Engineer Incharge.	P.Sft	
4	Allignment of Steel Tank with sporting Angle iron 1½" x 1½"x¼" including welding etc complete as directed by Engineer Incharge.	P.M	
5	Appoxi painting to Steel Tank (only internal side) as directied by Engineer Incharge.	P.Sft	
6	Painting or red oxide on old corrugated surfaces, pent roofing etc. with oil paint : Each subsequent coat (02 coats) as directed by Engineer Incharge..	P.M2	

SIGNATURE OF CONTRACTOR