

N.O.W: **Supply and Fixing of 2" dia G.I Pipe Line from Source to Tank and Construction of Collection Sump at Dungagali.**

Estimated Cost: Rs.1,073,000/-
 E/Monery: Rs.21,460/-
 Time Limit: 30th June, 2016.

BILL OF QUANTITY.

S.NO.	DESCRIPTION.	UNIT	RATE
1	Dismantling tees, bends or sluice valves upto 12" i/d	No.	
2	Dismantling : Plain Cement Concrete 1:4:8		
3	Dismantling : Plain Cement Concrete 1:2:4	M3	
4	Dismantling stone masonry in lime or cement mortar	M3	
5	Excavation in foundation of building, bridges etc complete : in ordinary soil	M3	
6	Providing and Laying cut, joint, test & disinfect GI pipe line Using light quality GI Pipe : 2" i/d	M	
7	Providing and Fixing gun metal peet / gate valve (screwed) 2" dia	No.	
8	RCC manhole cover 22" dia with: 3"x3"x1/4" angle iron frame, 22" i/d complete	No.	
9	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:4:8)	M3	
10	Coursed rubble masonry (Hammer Dressed) in foundn. & plinth in cement,sand mortar : Ratio 1:3	M3	
11	Plain Cement Concrete including placing, compacting, finishing & curing (1:2:4) as in bed	M3	
12	RCC in roof slab, beam, column & other structural members, insitu or precast. Type C (1:2:4)	M3	
13	Supply & fabricate M.S. reinforcement for cement concrete (Hot rolled deformed bars Grade 40)	Tonne	
14	Cement plaster 1:3 upto 20' height 3/4" thick	M2	
15	Supplying and Fixing MS manhole cover of 0.25" thick sheet & angle iron frame 2"x2"x0.25" with lock complete	M2	
16	Providing, laying, cutting, jointing, testing and disinfecting light quality G.I pipe including G.I specials as per PHED standard specifications of 2" dia G.I Pipe for wash out / over flow.	M	

Note: Any item of work not reflected in the BOQ and necessarily required to be executed at the site will be paid as per approved provision according to MRS-2015 Qtr-2 or Market rates approved by engineer incharge and duly covered in the Technical Sanction.

CONTRACTOR'S STAMP / SIGNATURE