

SUPPLY AND FIXING G.I PIPE LINES AT GHORADAKKA AND KHANSPURN.O.W: **AYUBIA.**

Estimated Cost: Rs.3,520,000
Earnest Money: Rs.70,420
Time Limit: 03 Months.

BILL OF QUANTITY.

S.NO.	DESCRIPTIN	UNIT	AMOUNT
1	Dismantling tees, bends or sluice valves upto 12" i/d	M3	
2	Dismantling : Plain Cement Concrete 1:4:8	M3	
3	Dismantling : Plain Cement Concrete 1:2:4	M3	
4	Dismantling stone masonry in lime or cement mortar	M3	
5	Excavation in foundation of building, bridge etccomplete: in ordinary soil	M3	
6	Providing and Laying cut, joint, test & disinfect GI pipe line Using light quality GI Pipe : 3" i/d	M	
7	Providing and Laying cut, joint, test & disinfect GI pipe line Using light quality GI Pipe : 1.5" i/d	M	
8	Providing and Fixing gun metal peet / gate valve (screwed)2" dia	No.	
9	RCC manhole cover 22" dia with: 3"x3"x1/4" angle iron frame, 22" i/d complete	Set.	
10	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:4:8)	M3	
11	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:2:4)	M3	

Note: Any item of work not reflected in the BOQ and necessarily required to be executed at the site will be paid as per approved provision according to MRS-2015 Qtr-2 or Market rates approved by engineer incharge and duly covered in the Technical Sanction.

STAMP & SIGNATURE OF CONTRACTOR: