

N.O.W: Supply and Fixing of 2" dia G.I Pipe Line from Church to Shangrilla Pine Nathiagali.

Estimated Cost : Rs.1,055,000/-
Earnest Money: Rs.21000/-
Time Limit: 2 Months.

BILL OF QUANTITY.

| S.NO. | DESCRIPTION | UNIT | RATE |
|--------------|---|-------------|-------------|
| 1 | Dismantling tees, bends or sluice valves upto 12" i/d | M3 | |
| 2 | Dismantling : Plain Cement Concrete 1:4:8 | M3 | |
| 3 | Dismantling : Plain Cement Concrete 1:2:4 | M3 | |
| 4 | Dismantling stone masonry in lime or cement mortar | M3 | |
| 5 | Excavation in foundation of building, bridges etc complete: in ordinary soil | M3 | |
| 6 | Providing and Laying cut, joint, test & disinfect GI pipe line Using light quality GI Pipe : 2" i/d | M | |
| 7 | Providing and Fixing gun metal peet / gate valve (screwed) 2" dia | No. | |
| 8 | RCC manhole cover 22" dia with: 3"x3"x1/4" angle iron frame, 22" i/d complete | Set. | |
| 9 | Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:4:8) | M3 | |
| 10 | Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:2:4) | M3 | |

Note: Any item of work not reflected in the BOQ and necessarily required to be executed at the site will be paid as per approved provision according to MRS-2015 Qtr-2 or Market rates approved by engineer incharge and duly covered in the Technical Sanction.

STAMP & SIGNATURE OF CONTRACTOR.