CONSTRUCTIOFN OF P.C.C ROAD BARRIAN / KALABIN FROM COLLEGE ROAD U/C NATHIAGALI ABBOTTABAD (1 KM).

N.O.W:

BILL OF QUANTITY.

			Estimaed Cost. Earnest Money. Time Limit.		Rs.4,110,000/- Rs.82,200/- 06 Months	
<u>S.No</u>	<u>Description</u>		<u>Unit</u>	<u>Qty:</u>	<u>Rate</u>	Amount
1	Excavation in shingle or gravel formation & rock not requiring blast, undressed, 50m lead : Dry	03-11-a	М3	442	220.5	Rs.97,461/-
2	Cement Concrete (brick/stone ballast, 1.5" to 2"/nullah shingle well graded and cleaned) in foundation & plinth (Ratio 1:4:8)	06-03-b	М3	279	4973.99	Rs.1,387,743/-
3	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:2:4)	06-05-f	M3	279	8358.28	Rs.2,331,960/-
MASONRY WORK:-						
1	Structural Excavation in Common Material	03-67-a-i	М3	10.872	233.63	Rs.2,540/-
2	Cement Concrete (brick/ stone ballast, 1.5" to 2"/ nullah shingle well graded and cleaned) in foundation & plinth(Ratio 1:4:8)	06-03-b	М3	2.25	4,973.99	Rs.11,191/-
3	Random rubble masonry in foundn. & plinth in cement, sand mortar : Ratio 1:6	08-01-d-03	М3	20.4	6,960.26	Rs.141,989/-
4	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:2:4)	06-05-f	M3	0.54	8,358.28	Rs.4,513/-
5	Structural backfill using Common Material available at site.	03-67-c	М3	7.2	315.48	Rs.2,271/-
6	Pointing flush on stone work, upto 20' height On stone work raised : in c/s mortar 1:3	11-19-c-02	M2	24	476.37	Rs.11,433/-
	TOTAL =					Rs.3,991,103/-
	Multiplied by 1.03 cost Factor for Districtr Abbottabad.					Rs.119,733/-
TOTAL =						Rs.4,110,836/-

Note: All unforceen items which not includes in this BOQ will be pay to the contractor on his existing quoted premium on MRS-2019.

I offer my Premium ______ % Above / Below / At Par on MRS-2019.

CONTRACTOR'S STAMP/SIGNATURE.