

CONSTRUCTION OF VALLEY BALL COURT AT KHANASPUR

BILL OF QUANT ITY.

Estimated Cost

Rs.0.612 (M)

E/ Money

Rs.12300/-

Time Limit

03 Months

<u>S.#</u>	<u>Description</u>	<u>Unit</u>	<u>Rate</u>	<u>Qty:</u>	<u>Amount</u>
1	Levelling, dressing and making lawns.	M2	31.22	217.47	Rs.6,789/-
2	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:2:4)	M3	7783.07	24.66	Rs.191,931/-
3	Random rubble masonry in ground floor in cement,sand mortar : Ratio 1:6.	M3	7007.91	20.05	Rs.140,509/-
4	Damp proof course of cem. conc. 1:2:4 including bitumen coat, 1 layer polythene & 1 coat bitumen (1.5" thick)	M2	822.27	32.91	Rs.27,061/-
5	Random rubble masonry in ground floor in cement,sand mortar : Ratio 1:3	M3	7,850.95	13.37	Rs.104,967/-
6	Cement plaster 1:4 upto 20' height 3/8" thick.	M2	273.04	32.91	Rs.8,986/-
7	Cement Concrete (brick/stone ballast, 1.5" to 2"/nullah shingle well graded and cleaned) in foundation & plinth (Ratio 1:3:6).	M3	5,921.98	4.96	Rs.29,373/-
8	Providing and Fixing GI pipe & including specials complete 2" dia (light).	M	1,043.22	6.71	Rs.7,000/-
9	Providing & Fixing of Volley Ball Net (NSI).	No	2,500.00	1.00	Rs.2,500/-
10	Pointing flush on stone work, upto 20' height in cement sand mortar 1:3.	M2	263.81	65.80	Rs.17,359/-
11	Providing and fixing of basket ball pole with Ring/ Wooden board. (NSI)	No	30,000.00	2.00	Rs.60,000/-
TOTAL				=	Rs.596,474/-
Add 3% cost factor except non shedule items				=	Rs.16,017/-
TOTAL				=	Rs.612,491/-

Note: All unforeseen items which are not mentioned in this BOQ will be paid to contractor on their existing quoted premium on MRS-2020

I Offer My Premium _____% Below/ Above/ At Par On Schedule Items.

I Offer My Premium _____% Below/ Above/ At Par On Non Schedule Items.

SIGNATURE OF THE CONTRACTOR: