

**BILL OF QUANTITY.**

Estimaed Cost. 2.50 (M)  
 Earnest Money. Rs.50,000/-  
 Time Limit. 02 Months

S.#	Description	Unit	Qty:	Rate	Amount
1	Rock Excavation, dressing & disposal up to 50m Medium hard rock, requiring occasional blasting	P.M3	217	811.78	Rs.176,156/-
2	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:2:4)	P.M3	268	7,783.07	Rs.2,085,863/-
3	Structural excavation in common material.	P.M3	10.87	259.41	Rs.2,820/-
4	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:4:8).	P.M3	2.25	6,004.18	Rs.13,509/-
5	Random rubble masonry in foundn. & plinth in cement, sand mortar : Ratio 1:6.	P.M3	20.40	6,683.45	Rs.136,342/-
6	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:2:4).	P.M3	0.55	7,783.07	Rs.4,281/-
7	Filling and Compacting Soil, Earth and Boulders behind retaining walls by mechanical means (Available material).	P.M3	7.2	248.57	Rs.1,790/-
8	Pointing flush on stone work, upto 20' height On stone work raised : in c/s mortar 1:3.	P.M2	13	461.42	Rs.5,998/-
<b>TOTAL</b>					<b>Rs.2,426,759/-</b>
Add 3% cost factor					Rs.72,803/-
<b>TOTAL</b>					<b>Rs.2,499,562/-</b>

Note: All unforceen items which not includes in this BOQ will be pay to the contractor on his existing quoted premium on MRS-2020

I offer my Premium \_\_\_\_\_ % Above / Below / At Par on MRS-2020.

I offer my Premium \_\_\_\_\_ % Above / Below / At Par on Non Schedule Items.

**CONTRACTOR' S STAMP / SIGNATURE.**