

N.O.W: **CONSTRUCTION OF PCC ROAD HOUSE OF BRIG. ARSHAD TO AJAB KHAN HOUSE, DONGAGALI U/C NATHIAGALI DISTRICT ABBOTTABAD**

BILL OF QUANT ITY.

Estimated Cost **Rs.1.290 (M)**
E/ Money **Rs.25,800/-**
Time Limit **06 Months**

<u>S.No</u>	<u>Description</u>	<u>MRS-2022 (2nd BI- Annual)</u>	<u>Unit</u>	<u>Rate</u>	<u>Qty:</u>	<u>Amount</u>
1	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:2:4)	06-05-f	P.M3	12745.86	68.92	Rs.878,445/-
2	Structural excavation in common material.	03-67-a-i	P.M3	347.98	18.12	Rs.6,305/-
3	Cement Concrete (brick/stone ballast, 1.5" to 2"/nullah shingle well graded and cleaned) in foundation & plinth (Ratio 1:4:8).	06-03-b	P.M3	8275.5	3.76	Rs.31,116/-
4	Random rubble masonry in foundn. & plinth in cement, sand mortar : Ratio 1:6	08-01-d-03	P.M3	9150.45	34	Rs.311,115/-
6	Structural backfill using Common Material available at site	03-67-c	P.M3	413.21	12	Rs.4,959/-
7	Pointing flush on stone work, upto 20' height On stone work raised : in c/s mortar 1:3	11-19-c-02	P.M2	620.08	40	Rs.24,803/-
	TOTAL				=	Rs.1,256,743/-
	Add 3% Cost Factor for District Abbottabad				=	Rs.37,702/-
	TOTAL				=	Rs.1,294,445/-

Note: All unforeseen items which are not mentioned in this BOQ will be paid to contractor on their existing quoted premium.

I Offer My Premium _____% Below/ Above/ At Par On Schedule Items on MRS-2022 (2nd BI-Annual)

I Offer My Premium _____% Below/ Above/ At Par On Non Schedule Items

SIGNATURE OF THE CONTRACTOR: