N.O.W:

Construction of PCC Road Badiar near house of Saeed Khan U/C Nathiagali District Abbottabad.

BILL OF QUANT ITY.

Estimated Cost Rs.4.980 (M)

E/ Money Rs.99,600/
Time Limit 06 Months

S.No	Description	MRS-2022 (2nd BI- Annual)	<u>Unit</u>	<u>Rate</u>	Qty:	<u>Amount</u>
1	Dressing & levelling earth to designed section Gravel work or soft rock not requiring blasting upto cut or fill 6 inches.	03-21-с	P.M3	50.56	1835.00	Rs.92,778/-
2	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:2:4)	06-05-f	P.M3	12745.86	307.15	Rs.3,914,891/-
3	Structural excavation in common material.	03-67-a-i	P.M3	347.98	25.375	Rs.8,830/-
4	Cement Concrete (brick/stone ballast, 1.5" to 2"/nullah shingle well graded and cleaned) in foundation & plinth (Ratio 1:4:8).	06-03-b	P.M3	8275.5	7.25	Rs.59,997/-
5	Random rubble masonry in foundn. & plinth in cement, sand mortar: Ratio 1:6	08-01-d-03	P.M3	9150.45	76.88	Rs.703,441/-
6	Structural backfill using Common Material available at site	03-67-с	P.M3	413.21	32	Rs.13,223/-
7	Pointing flush on stone work, upto 20' height On stone work raised : in c/s mortar 1:3	11-19-c-02	P.M2	620.08	75	Rs.46,506/-
	TOTAL Add 3% Cost Factor for District Abbottabad				=	Rs.4,839,665/-
				oad	=	Rs.145,190/-
	TOTAL				=	Rs.4,984,855/-

Note:	All unforseen items which are not mentioned in this BOQ will be paid to contractor on their existing quoted premium.					
	I Offer My Premium (2nd BI-Annual)	% Below/Above/At Par On Schedule Items on MRS-2022				
	I Offer My Premium	% Below/Above/At Par On Non Schedule Items				

SIGNATURE OF THE CONTRACTOR:

N.O.W: Widening of Shingle Road Donglian Gali Mohallah Hotar Patan Kalan 2 Km

BILL OF QUANT ITY.

 Estimated Cost
 Rs.3.801 (M)

 E/ Money
 Rs.76,002/

 Time Limit
 06 Months

S.No	Description	MRS-2022 (2nd BI- Annual)	<u>Unit</u>	Rate	Qty:	<u>Amount</u>
	Excavation in foundation of building, bridges etc complete : in shingle/gravel	03-25-d	P.M3	421.14	4643	Rs.1,955,353/-
1	Dressing & levelling earth to designed section Gravel work or soft rock not requiring blasting upto cut or fill 6 inches.	03-21-с	Р.М3	50.56	836	Rs.42,268/-
3	Structural excavation in common material.	03-67-a-i	P.M3	347.98	50.75	Rs.17,660/-
4	Cement Concrete (brick/stone ballast, 1.5" to 2"/nullah shingle well graded and cleaned) in foundation & plinth (Ratio 1:4:8).	06-03-b	P.M3	8275.5	14.5	Rs.119,995/-
5	Random rubble masonry in foundn. & plinth in cement, sand mortar: Ratio 1:6	08-01-d-03	P.M3	9150.45	153.75	Rs.1,406,882/-
2	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:2:4)	06-05-f	P.M3	12745.86	2.3	Rs.29,315/-
6	Structural backfill using Common Material available at site	03-67-с	P.M3	413.21	64	Rs.26,445/-
7	Pointing flush on stone work, upto 20' height On stone work raised : in c/s mortar 1:3	11-19-c-02	P.M2	620.08	150	Rs.93,012/-
	TOTAL Add 3% Cost Factor for District Abbottabad				=	Rs.3,690,931/-
				ad	=	Rs.110,728/-
	TOTAL				=	Rs.3,801,658/-

Note:	All unforseen items which are not mentioned in this BOQ will be paid to contractor on their existing quoted premium.					
	I Offer My Premium (2nd BI-Annual)	% Below/Above/At Par On Schedule Items on MRS-2022				
	I Offer My Premium	% Below/Above/At Par On Non-Schedule Items				

N.O.W:

Note:

Construction Of PCC Approach Road/Retaining Wall Near House of Saeed Khan U/C Nathiagali District Abbottabad

BILL OF QUANT ITY.

 Estimated Cost
 Rs.3.800 (M)

 E/ Money
 Rs.76,000/

 Time Limit
 06 Months

					1	<u>oo montis</u>	
S.No	Description	MRS-2022 (2nd BI- Annual)	<u>Unit</u>	Rate	Qty:	Amount	
1	Dressing & levelling earth to designed section Gravel work or soft rock not requiring blasting upto cut or fill 6 inches.	03-21-с	P.M3	50.56	917	Rs.46,364/-	
2	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:2:4)	06-05-f	P.M3	12745.86	155.3	Rs.1,979,432/-	
3	Structural excavation in common material.	03-67-a-i	P.M3	347.98	50.75	Rs.17,660/-	
4	Cement Concrete (brick/stone ballast, 1.5" to 2"/nullah shingle well graded and cleaned) in foundation & plinth (Ratio 1:4:8).	06-03-b	P.M3	8275.5	14.5	Rs.119,995/-	
5	Random rubble masonry in foundn. & plinth in cement, sand mortar: Ratio 1:6	08-01-d-03	P.M3	9150.45	153.75	Rs.1,406,882/-	
6	Structural backfill using Common Material available at site	03-67-с	P.M3	413.21	64	Rs.26,445/-	
7	Pointing flush on stone work, upto 20' height On stone work raised : in c/s mortar 1:3	11-19-c-02	P.M2	620.08	150	Rs.93,012/-	
	TOTA	L	91		= Rs.3,689,789		
	Add 3% Cost Factor for District Abbottabad					Rs.110,694/-	
	TOTAL			-	Rs.3,800,483/-		

existing quoted premium.	ire not mentioned in this bod will be paid to contractor on the
I Offer My Premium (2nd BI-Annual)	% Below/Above/At Par On Schedule Items on MRS-2022
I Offer My Premium	% Below/Above/At Par On Non Schedule Items

N.O.W:

Note:

Construction Of PCC Road Raees Khana College Road U/C Nathiagali District Abbottabad (0.9 Km).

BILL OF QUANT ITY.

Estimated Cost Rs.4.796 (M)

E/ Money Rs.95,920/
Time Limit 06 Months

S.No	<u>Description</u>	MRS-2022 (2nd BI- Annual)	<u>Unit</u>	<u>Rate</u>	Qty:	Amount
1	Dressing & levelling earth to designed section Gravel work or soft rock not requiring blasting upto cut or fill 6 inches.	03-21-с	P.M3	50.56	917	Rs.46,364/-
2	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:2:4)	06-05-f	P.M3	12745.86	155.53	Rs.1,982,364/-
3	Structural excavation in common material.	03-67-a-i	P.M3	347.98	135.85	Rs.47,273/-
4	Cement Concrete (brick/stone ballast, 1.5" to 2"/nullah shingle well graded and cleaned) in foundation & plinth (Ratio 1:4:8).	06-03-b	P.M3	8275.5	22.99	Rs.190,254/-
5	Random rubble masonry in foundn. & plinth in cement, sand mortar: Ratio 1:6	08-01-d-03	P.M3	9150.45	242	Rs.2,214,409/-
6	Structural backfill using Common Material available at site	03-67-с	P.M3	413.21	99	Rs.40,908/-
7	Pointing flush on stone work, upto 20' height On stone work raised : in c/s mortar 1:3	11-19-с-02	P.M2	620.08	220	Rs.136,418/-
	TOTAL =					Rs.4,657,988/-
	Add 3% Cost Factor for 1	3% Cost Factor for District Abbottabad = Rs.13				Rs.139,740/-
	TOTAL				=	Rs.4,797,728/-

All unforseen items which existing quoted premium.	are not mentioned in this BOQ will be paid to contractor on their
I Offer My Premium (2nd BI-Annual)	% Below/Above/At Par On Schedule Items on MRS-2022
I Offer My Premium	% Below/Above/At Par On Non Schedule Items